amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, SPRINKLERS - 10
APM Object	FIRE.SUP.SPRK
APM EC	AMZ.FIRE.SPRK
BBM Handbook Title	Sprinkler System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SUPPRESSION			**Assets included in this PM:**	SPRINKLERS	**Schedule With:**	FIRE.SUP.WTRTNK FIRE.SUP.VALV FIRE.SUP.WETRISERS FIRE.SUP.HDRNT		

Description of System / Technology (According to BBM Handbook)

Fire sprinkler systems are active fire protection methods, consisting of a water supply system providing adequate pressure and flowrate to a water distribution piping system, to which fire sprinklers are connected.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						PM				
2	Safety	Are all safety devices, are correctly installed and free from damage (e.g., pressure relief devices)						PM				
3	Safety	Ensure that inspection valves has been positioned and locked as per AMZ standard						PM				
4	Sprinkler house/room	Is the entrance freely accessible & free of obstacles		PM								
5	Sprinkler house/room	Is there any visual damage or excessive vegetation at the building or around						PM				
6	Sprinkler house/room	Verify that the roof and roof drainage systems are free from damage and clogging						PM				
7	Sprinkler house/room	Check if the lightning protection is fixed appropriately & not damaged Forecast FPM against Lightning Protection						PM				
8	Sprinkler house/room	Is the door locked properly - protection against unauthorized entry		PM								
9	Sprinkler house/room Indoor	Is the light functioning and the room is illuminated properly		PM								
10	Sprinkler house/room Indoor	Is the heater & temperature control functioning correctly (freezing protection)		PM								
11	Sprinkler house/room Indoor	Check heater for dirt, damage, corrosion		PM								
12	Sprinkler house/room Indoor	Are there any water leaks visible at the walls or ceiling		PM								
13	Sprinkler house/room Indoor	Are there any visible leaks of the sprinkler system		PM								
14	Sprinkler house/room Indoor	Inspect the condition of all visible pipes, hangers, attachments and seismic bracing					PM	PM				
15	Electrical components	Are all metal parts connected to the protection earth (ground)						PM				
16	Panel	Check if there are any alarms, warnings etc indicated on the control panels (If dedicated panel installed)		PM								
17	Panel	Check circuit diagrams for completion (If dedicated panel installed)						PM				
18	Panel	If anything is missing or unclear in the circuit diagrams create a WO (If dedicated panel installed)						PM				
19	Panel	Are all cables properly routed (If dedicated panel installed)						PM				
20	Panel	Are all cables, terminal blocks & devices properly labeled or marked (If dedicated panel installed)						PM				
21	Panel	Test all safety relevant switches (If dedicated panel installed)						PM				
22	Panel	Were any obvious changes made (e.g. rewiring, hanging cables) (If dedicated panel installed)						PM				
23	Panel	Visual check for the protection against direct contact with live part (If dedicated panel installed)						PM				
24	Panel	Tight cable connections in the control cabinets & main supply connection boxes (If dedicated panel installed)						PM				
25	Panel	Are all metal parts connected to the protection earth (ground) (If dedicated panel installed)						PM				
26	Panel	Replace the air filters of the cabinet & check operation of cooling fan (If dedicated panel installed)						PM				
27	Thermographic scan	Perform thermographic scans & create a WO for over-temperature to determine the root cause (If dedicated panel installed)						PM				
28	Thermographic scan value	Add a detailed note for all over-temperature measurements -> list the location and temperature -> Upload the thermographic scan (If dedicated panel installed)						PM				
29	Sprinkler system	Inspect the condition of all visible pipes, hangers, attachments and seismic bracing						PM				
30	Sprinkler system	Inspect condition of sprinkler heads for signs of damage, corrosion & risks that could trigger an FFA						PM				
31	Sprinkler system	Conduct a full functional test of the sprinkler system, including alarm system						PM				
32	Sprinkler system	Inspect the condition of all visible pipes, hangers, attachments and seismic bracing for corrosion, damage, or wear						PM				
33	Sprinkler system	Verify the hydraulic design data, including flow & pressure requirements						PM				
34	Sprinkler system	Release condensate water from any dry pipe string						PM				
35	Spare parts	Check the condition of spare sprinklers, ensure they are properly stored & available for the SME in case needed						PM				

36	Spare parts	Check the condition of special tools, ensure they are properly stored & available for the SME in case needed						PM					
37	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM					

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed 1M and 3M and added 6M.Added tasks due to HIE (FFA).