amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, WATER STORAGE TANKS - 10
APM Object	FIRE.SUP.WTRTNK
APM EC	AMZ.FIRE.WT
BBM Handbook Title	Water Storeage Tanks
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SUPPRESSION	**Assets included in this PM:**	WATER STORAGE FIRE TANKS	**Schedule With:**	FIRE.SUP.SPRK FIRE.SUP.VALV FIRE.SUP.WETRISERS FIRE.SUP.HDRNT				

Description of System / Technology (According to BBM Handbook)

Emergency supply of water for fire suppression equipment e.g. Sprinkler System

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Tank	Record the tank temperature in °C		PM								
2	Tank	Check if the tank is filled correctly (correct water level)		PM								
3	Tank	Check if all tank equipment is free from damage, rust & corrosion, fixed properly & leak-free		PM								
4	Tank	Check the tank relief valve or overflow for correct function						PM				
5	Tank	Verify proper functioning of the tank and pipe heaters						PM				
6	Tank	Does the Sprinkler tank has a free flow inlet separation and can`t contaminate the drinking water						PM				
7	Hygiene	Carry out a CCTV check for debris inside the tank						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New PM for FIRE.SUP.WTRTNK.
Aug 2024 - Added task to verify correct function tank and pipe heating after lesson learned during site visit