amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, AIR CONDITION - 9
APM Object	HVAC.AC
APM EC	AMZ.HVAC.AC.GRP
BBM Handbook Title	Air Conditioning and Air Condensing (VRF / DX) Units
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Yes	**Activies may be covered by No-Go restrictions:**	Yes	**Special Certificaion Required:**	Refrigeration certificate could be required	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	9	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	AIR CONDITIONER UNIT	**Schedule With:**	HVAC.CU		

Description of System / Technology (According to BBM Handbook)

Air Condition (AC unit- indoor)
An air conditioning system is used to cool down the temperature in an inside space by removing the existing heat and moisture from the room.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
This PM covers the direct evaporating & water supplied fan-coil units installed inside the building in the offices & shop floor. (AC system - e.g. single split, multi split, VRF, VRV, etc.)

Note : Forecast the PM for the indoor (AC.ACU) & outdoor (AC.CU) units together and combine it with regulatory tasks (e.g. leakage test F Gas regulation)

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the documentation of installed BBA available & complete						PM				
2	General	Is the unit freely accessible & maintainable					SC	PM				
3	Measurement	Is the fan coil unit operating correctly (speed & temperature)					SC	PM				
4	Unit operation	Are there any obvious leakage of condensated water					SC	PM				
5	Unit operation	Check the fan for unusual noises (e.g. imbalance & bearing damage)					SC	PM				
6	Hygiene & Filter	Clean reusable filter or exchange disposable filter 80% of the capacity is reached					SC	PM				
7	Hygiene & Filter	Clean air inlet & outlet frames & surrounding surfaces						PM				
8	Hygiene & Filter	Clean impeller (fan) & reachable surfaces						PM				
9	Hygiene & Filter	Spray AC disinfection into running unit (coil disinfection)						PM				
10	Hygiene & Filter	Check Textile air hose for damage, contamination & dirt					SC	PM				
11	Hygiene & Filter	Schedule exchange or washing of the textile air hose if necessary					SC	PM				
12	Pipe system	DX unit - refrigeration pipes & connections for corrosion & oil build up (leakage)						PM				
13	Pipe system	Water supplied unit - Check pipes & connections for corrosion & leakage						PM				
14	Pipe system	Water supplied unit - Check control valves for correct functionality						PM				
15	Pipe system	Water supplied unit - Check pipe filters for free flow						PM				
16	Pipe system	Check Pipe insulation for damage						PM				
17	Drain	Check condensate pump & condensate pipes for correct operation, damage						PM				
18	Drain	Does the condensate pipe has a free outlet to the drainage (not connected directly to drainage)						PM				
19	Final Check	Check the O&M manual and carry out additional required tasks						PM				
1	General check & Documentation	Is the unit freely accessible & maintainable						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed task "Is there ice build on the coil -> if yes eliminate root cause"