amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, BOILER UNITS - 9
APM Object	HVAC.BLR
APM EC	AMZ.HVAC.BLR.GRP
BBM Handbook Title	Boiler Units (natural gas)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	9	**Related CT Areas:**	CT.HVAC.BOILERS			**Assets included in this PM:**	NATURAL GAS BOILER UNIT	**Schedule With:**	HVAC.RTU HVAC.AHU HVAC.WTR HVAC.GH		

Description of System / Technology (According to BBM Handbook)

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: the yearly PPM should be planned before the summer season starts.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: The PM should be carried out before the heating / winter season starts.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the boiler documentation complete & are there drawings on the wall						PM				
2	Visual check	Are installations damaged or loose (incl. cables connected to equipment)						PM				
3	Gas Burner	Check the gas burner for correct function and leakage (burner & exhaust)						PM				
4	Visual check	Check any flexible gas pipes and connections for damage or leakage						PM				
5	Boiler check	Check the sequence of operation of the burner						PM				
6	Boiler check	Check the combustion fan and proceed to the cleaning						PM				
7	Boiler check	Check the pressure of the gas supplying the unit						PM				
8	Boiler check	Check the state of the flame						PM				
9	Boiler check	Perform a flue gas analysis						PM				
10	Final Check	Undertake inspection and maintenance in line with O&M + local regulations						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New tasks added. Included "forecast with".