amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, KITCHEN EXHAUST DUCT SYSTEM - 9
APM Object	HVAC.DH
APM EC	AMZ.HVAC.DH
BBM Handbook Title	Kitchen Exhaust Duct System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	9	**Related CT Areas:**	CT.ENVIRO.EXTRACT			**Assets included in this PM:**	KITCHEN EXHAUST DUCT SYSTEM	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

A Kitchen Exhaust Duct System is a set of components that remove smoke, heat, and odors from a commercial kitchen or cooking area. Typically the system consists of an exhaust hood, fan, duct and vent, all working together to ventilate the smoke and odors to the outside.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Ensure that the kitchen exhaust duct cleaning is carried out according to loacal rgulations/requirements

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the documentation of the system complete & available					PM					
2	Duct system	Is there any damage or corrosion at the exhaust hoods or duct system visible			SC		PM					
3	Duct system	Is the inner duct system free from grease deposit			SC		PM					
4	Duct system	Schedule duct system & exhaust fan cleaning in case of thig grease deposit (fire hazard)			SC		PM					
5	Duct system	Clean inner duct system, hoods & exhaust fan At least once in every 6 months of operation - use state-of-art technology					PM					
6	Electrical & fan condition	Is the power consumption of the fan as per manufacturer`s specs (after cleaning)					PM					
7	Electrical & fan condition	Does the fan make unusual noises or vibration			SC		PM					
8	Electrical & fan condition	The cooking devices & dishwashers switch off in case of missing exhaust airflow					PM					
9	Electrical & fan condition	Change the belt of the exhaust fan (if belt driven)					PM					
10	Electrical & fan condition	Check other mechanical components like pulleys and bearings for defects					PM					
11	Measurement	Measure the airflow of the kitchen exhaust & compare to design					PM					
12	Final Check	Check the O&M manual and carry out additional required tasks					PM					

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.