amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, EXHAUST FAN UNITS - 9
APM Object	HVAC.EF
APM EC	AMZ.HVAC.EF.GRP
BBM Handbook Title	Exhaust Fan
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	9	**Related CT Areas:**	CT.AIR.ENCSPACE			**Assets included in this PM:**	EXHAUST FANS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Exhaust fans are generally connected to the roof and operate to discharge warm internal air to the outside atmosphere. There are used in Amazon FC's to cool the FC space before active cooling is initiated.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Ensure that the kitchen exhaust duct cleaning is carried out according to loacal rgulations/requirements

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the documentation of the system complete & available						PM				
2	General	Check the room for unusual odur from e.g., drainage Create action to eliminate the root cause				SC	PM	PM				
3	Duct system	Check inner duct system, exhaust intakes (rooms) & exhaust outlet (fan) Scheule cleaning if blocked or in case of high accumulation of dirt						PM				
4	Duct system	Check inner duct system for blockages & extensive dirt accumulation 30% of the outlets 1m of the system - Ensure correct rotation						PM				
5	Measurement	Is the power consumption of the fan as per manufacturer`s specs						PM				
6	Measurement	Measure the airflow of the exhaust & compare to design						PM				
7	Electrical & fan condition	Does the fan make unusual noises or vibration				SC	PM	PM				
8	Electrical & fan condition	Change the belt of the exhaust fan (if belt driven)					PM	PM				
9	Electrical & fan condition	Check other mechanical components like pulleys and bearings for defects					PM	PM				
10	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.