amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, HUMIDIFIERS - 9
APM Object	HVAC.HMD
APM EC	AMZ.HVAC.HMD.GRP
BBM Handbook Title	Humidifier
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	Hygiene certification required in some countries (e.g. VDI 6022)	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	9	**Related CT Areas:**	CT.WATER.COOLINGTOWERS			**Assets included in this PM:**	HUMIDIFIER UNIT	**Schedule With:**	HVAC.RTU HVAC.AHU		

Description of System / Technology (According to BBM Handbook)

A device to add moisture to air or gases. The device must be standalone, not internal nor auxiliary to another technology (ie :RTU).

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: the yearly PPM should be planned before the summer season starts.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the technical documentation & blueprints of installed system available & complete						PM		PM		
2	Humidifier	Check for correct function of all safety & additional shut down devices					SC	PM		PM		
3	Humidifier	Carry out a functional check of the humidifier (incl. control valves & moisture limiter)			SC		SC	PM		PM		
4	Humidifier	Check all components & surfaces for damage, deposit & corrosion						PM		PM		
5	Humidifier	Check all pipes, hoses & atomizer nozzles for deposits and damage			SC		SC	PM		PM		
6	Humidifier	Check the pump for correct function if installed					SC	PM		PM		
7	Humidifier	Check the function of the blow-down device					SC	PM		PM		
8	Humidifier	Check conductivity-critical cell for function			SC		SC	PM		PM		
9	Humidifier	Check the function of the sterilization system if installed						PM		PM		
10	Humidifier	Check for precipitation in the humidification chamber			SC		SC	PM		PM		
11	Humidifier	Check steam lance for deposits					SC	PM		PM		
12	Humidifier	Ensure that microbiological tests are carried out according to local requirements					SC	PM		PM		
13	Final Check	Check the O&M manual and carry out additional required tasks						PM		PM		

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New PM, moved these tasks from the HVAC.AHU PM according to the last OCB updates. Added "forecast with".ç