amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, SUPPLY FAN UNITS - 9
APM Object	HVAC.SUP
APM EC	AMZ.HVAC.FAN.GRP
BBM Handbook Title	Supply Fans
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Dec-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	NO	**Pricing template Position:**	9	**Related CT Areas:**	CT.AIR.INDOOR	**Assets included in this PM:**	SUPPLY FANS	**Schedule With:**	-				

Description of System / Technology (According to BBM Handbook)

Ceiling fans, with a minimum blade diameter of 4 feet/1.5 meters, circulate the air within the building space. System includes High Volume, Low Speed (HVLS) are considered as supply fans.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Electrical Panel	Check whether an alarm is dispalyed If applicable					SC	PM				
2	Visual check	Visual check from the ground for visible damage at the fan (e.g. loose parts)					SC	PM				
3	Visual check	Visual check from the ground wether the fan is working properly					SC	PM				
4	Visual check	Are there any unusual noise of the bearing, motor, blades or other Test while in operation						PM				
5	Visual check	Check the fan for unbalance Test while in operation						PM				
6	Visual check	Check whether the electrical wires/cables are free from damage and fixed properly						PM				
7	Visual check	Check whether the fan is mounted correctly/firmly Tighten as required according to manufacturer guideline						PM				
8	Visual check	Check whether the safety cable is properly secured/attached to prevent the fan from falling						PM				
9	Visual check	Check whether the fan blades are properly attached Tighten as required according to manufacturer guideline						PM				
10	Visual check	Inspect motor/gearbox for oil leaks If present consult manufacturer						PM				
11	Functional cleaning	Clean fan blades to maintain functionality						PM				
12	Measurement	Measure power consumption & compare to manufacturer specification If possible & on the ground						PM				
13	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.