amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, WATER HEATED SYSTEM - 9
APM Object	HVAC.WTR
APM EC	AMZ.HVAC.WTR.GRP
BBM Handbook Title	Water Heated System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	Trained Plumber and certified electrician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	9	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	WATER HEATED UNIT	**Schedule With:**	HVAC.BLR HVAC.GH		

Description of System / Technology (According to BBM Handbook)

A hot water heating system recirculates heated water through a system of pipes to radiators or air handler units, which then release the heat to the surrounding air. The water is usually heated by a boiler, which burns a fuel such as natural gas or oil to generate heat.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: The yearly PPM should be carried out before the start of the heating season (winter)

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the documentation of the heating system complete & are there drawings on the wall						PM				
2	Leakage check	Are there any visible water leakages at the heating water system						PM				
3	Unit check	Are technical installations damaged or loose (incl. cables connected to equipment)						PM				
4	Unit check	Are there any damage at pipe or equipment insulation (pipes, buffer, valves, etc.)						PM				
5	Hygiene & Safety	Is the drinking water separation working properly, free from damage & corrosion						PM				
6	Hygiene & Safety	Do the safety devices work as required (e.g. pressure relief valve)						PM				
7	Hygiene & Safety	Is the expansion tank function as intended						PM				
8	Hygiene & Safety	Ensure all valves to expansion are open & secured						PM				
9	Functional cleaning	Clean system filters & check for damage						PM				
10	Functional cleaning	Clean all fittings & other equipment to maintain their functionality						PM				
11	Measurement	Are there any damage at the thermostats and pressure manometer						PM				
12	Measurement	Are the values showing any indication of incorrect water flow						PM				
13	Measurements	Measure the power consumption of the pumps while operating on 100% Compare the power consumption with the manufacturer specification - react in case of deviation						PM				
14	System devices	Are the pumps working properly, are free from damage & corrosion						PM				
15	System devices	Are the motor driven valves working properly						PM				
16	System devices	Check balancing valves for correct function (Strangregulierung)						PM				
17	System devices	Test all manual control devices for correct function						PM				
18	System devices	Lubricate the spindle of all control fittings						PM				
19	System devices	Are the filling, emptying and sludge removal devices working correctly						PM				
20	System devices	Is the system pressure according to design (high enough to supply the building)						PM				
21	System devices	Check all temperatures for abnormalities which indicates a clogged heat exchanger, incorrect operating pumps, valve, etc.						PM				
22	System devices	Are automatic air vents working properly & are free from damage & corrosion						PM				
23	System devices	Manual air vents - release air at the possible locations of air bubbles in the system						PM				
24	System devices	Are expansion joints connected tightly & are free from damage						PM				
25	System devices	Check sacrificial anode (if installed)						PM				
26	System devices	Check buffer for damage & correct water level (no air, or damaged membrane)						PM				
27	System devices	Check correct function of electrical heaters						PM				
28	Electrical	Is the pipe trace heating working properly (if installed)						PM				
29	Radiator	Are the radiators working correctly & are free from damage & corrosion						PM				
30	Radiator	Are there obvious air bubbles in the radiator						PM				
31	Air curtain water supplied	Are all safety devices functioning correctly										
32	Air curtain water supplied	All components free for damage and live parts not accesible										
33	Air curtain water supplied	Is the unit functioning correctly										
34	Air curtain water supplied	Is there any unusual noise or vibration										
35	Air curtain water supplied	Is the unit leakage free										

36	Air curtain water supplied	Are the heating water supply valves functioning correctly											
37	Air curtain water supplied	Is the hot water supply valve adjusted correctly and free water flow possible to supply the heat exchanger properly											
38	Air curtain water supplied	Clean reusable filter or exchange disposable filter											
39	Controller & Control cabinet	Is the unit in operation & no alarms indicated - check unit control cabinet						PM					
40	Controller & Control cabinet	Are any settings in manual mode -clarify the reason & set back to automatic mode						PM					
41	Controller & Control cabinet	Did any circuit breaker trip - identify & eliminate the root cause or create a WO						PM					
42	Controller & Control cabinet	Visual check of the control cabinets inside & outside for damage, debris & missing components						PM					
43	Controller & Control cabinet	Check circuit diagrams for completion						PM					
44	Controller & Control cabinet	If anything is missing or unclear in the circuit diagrams create a WO						PM					
45	Controller & Control cabinet	Are all cables properly routed						PM					
46	Controller & Control cabinet	Are all cables, terminal blocks & devices properly labelled or marked						PM					
47	Controller & Control cabinet	Test all safety relevant switches						PM					
48	Controller & Control cabinet	Were any obvious changes made (e.g. rewiring, hanging cables)						PM					
49	Controller & Control cabinet	Visual check for the protection against direct contact with live part						PM					
50	Controller & Control cabinet	Tight cable connections in the control cabinets & main supply connection boxes						PM					
51	Controller & Control cabinet	Are all metal parts connected to the protection earth (ground)						PM					
52	Pumps	Can you identify unsusual noise or vibration of operating pumps						PM					
53	Pumps	Can you identify unsusual noise or vibration of operating pumps						PM					
54	System devices	Maintain all electrical heating devices according to O&M & local regulations (e.g. DIN VDE)						PM					
55	Final Check	Check the O&M manual and carry out additional required tasks						PM					

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Aligned the APM Object according to the last OCB updates.