amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	LIGHT, EXTERNAL - 11
APM Object	LIGHT.EXT
APM EC	AMZ.LIGHT.EXT
BBM Handbook Title	External Lighting
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.LIGHTING			**Assets included in this PM:**	EXTERNAL LIGHTS	**Schedule With:**	BLDG.EXT BLDG.EXTSURFACES BLDG.RAINCOLL BLDG.BUSSHELTER BLDG.GATEBARRIER		

Description of System / Technology (According to BBM Handbook)

Lighting located on the buildings external as well as in the Yard, carpark and grounds.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Lighting	Perform a functional cleaning of the exterior lights & check lights for correct function & damage					SC	SC				
2	Controller	For sites with lighting control systems installed (EIB, KNX, etc.) Check the controller for alarms, damage & correct function by changing setpoints and checking reactions of the system						SC				
3	Controller	Is the documentation of the system available and complete						SC				
4	Final Check	Check the O&M manual and carry out additional required tasks						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.