amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	STORAGE, HIGH RACKS - 14
APM Object	STOR.HRACK
APM EC	AMZ.HRACK.ZONE
BBM Handbook Title	High Racking
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	Operations
Evidence for CT:	TBC	**Pricing template Position:**	14	**Related CT Areas:**	CT.WORK.STORAGE			**Assets included in this PM:**	HIGH RACKS ZONE P1A	**Schedule With:**	STOR.SHELV		

Description of System / Technology (According to BBM Handbook)

All sites with high racks installed - Racking dimensions: 10m(L) X 10m(H) x 1m or standard pallet depth(D)

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documents	Is the documentation of the equipment available & complete						SC				
2	Frames	The frames does not show any deformation or other damage						SC				
3	Beam	The beams are free from damage						SC				
4	Rack supports	The rack support is upright, not deformed, not twisted & free from damage						SC				
5	Footplates	The footplates are all present and not deformed						SC				
6	Welds	Check the welds for cracks						SC				
7	Building floor	The floor of the building does not have tripping hazards, is level, anti-slip						SC				
8	Loads on the pallet	The loads do not exceed the maximum load. No deformation or deflection detectable						SC				
9	Position of the loading equipment	The load is secured from falling down and the loading equipment is placed in its fixed place.						SC				
10	Dimensions of the loading units	The dimensions correspond to those of the load plates.						SC				
11	Stability of the loading units	The loading units have all the necessary compartments for stabilization.						SC				
12	Attachment	All truss attachments and all required truss connections are in place.						SC				
13	Load tags	The load plates are attached in accordance with the regulations.						SC				
14	Final Check	Check the O&M manual and carry out additional required tasks						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.