amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	STORAGE, SHELVING - 14
APM Object	STOR.SHELV
APM EC	AMZ.SHELV
BBM Handbook Title	Picktower Shelving
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	14	**Related CT Areas:**	CT.WORK.STORAGE			**Assets included in this PM:**	SHELVES	**Schedule With:**	STOR.HRACK		

Description of System / Technology (According to BBM Handbook)

Picktower Shelving - Shelve dimensions: 1m(L) X 1m(H) X 1m(D)

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the documentation of the equipment available & complete						SC				
2	Building floor	he floor surrounding the shelves is free of tripping hazards						SC				
3	Shelf feet	Check the rack feet for collision protection, deformations and twists						SC				
4	Shelf feet	Ensure the shelf is securely anchored to the floor and all screws are tightened						SC				
5	Storage	The storage of the pallets/boxes must be checked for proper securing						SC				
6	Beam	The beams are free from damage						SC				
7	Weld	The welds for cracks and other damage						SC				
8	Load tags	Ensure the load plate and warning signs are properly attached in accordance with safety regulation						SC				
9	Final Check	Check the O&M manual and carry out additional required tasks						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
Aug 2024 - Added task to check for anchoring based on learnings from RME field